

BCLASSIC

12 MONTH CHECK UP! FRESHBREW/INSTANT

westomatic make it happen





<u>Key areas to look at:</u>

BOILER	 Remove and clean boiler probes De-scale boiler (if required) Replace boiler valves
WATER FILTER	 Replace water filter Calibrate water dispense flow rate - 0.6 Fl.oz/sec
WHIPPER DECK	 Clean extraction system Check all whipper motors are functioning correctly Replace whipper bases/seals/o-rings
BREWER	 Remove and clean Brewer For LPB: Clean LPB filter platform and replace filter belt
WATER TEMP	Perform machine flushEnsure there are no leaksCheck water temperature
MOVING DISPENSE HEAD	 Check moving dispense head is positioned correctly Nozzles align correctly with cup dispense area







westomatic

12 month Check up!

<u>Key areas to look at:</u>

CUP SENSOR	 Clean cup sensor Test operation of cup sensor - use your own cup Check cup drop operation and cup settings - placement time = 2secs, carousel timeout = 30 secs 	
TEST DRINKS	 Test a minimum of one drink of each type with machine door closed (with coins if coin mech fitted) Check drink quality by tasting 	

Safety Checks:

- **PAT test machine -** Insulation & Earth Bond only
- **Check Mains Lead** for damage/do not connect to extension lead
- **Check Fuses** correct value and type (remove fuses where not needed eg refrigeration fuse)
- **Check Looms** connections are free from damage and fully secured



Tools Required

PAT Tester Digital Thermometer Portable Hoover Gram Scales M4 (7mm) socket Cross Head Screwdriver



Estimated Labour Time - 1.25hrs



